

**S N Rane**  
**Executive Engineer**



June 01, 2022  
Ref. NIA/ENGG/2022-23/01

---

Balewadi, Baner Road, NIA P.O.,  
Pune 411 045 (India).  
Tel. (D): 020-27204047  
Tel. (O): 020 – 27204000 / 27204444  
Fax: 020-27204555  
Email: [snrane@niapune.org.in](mailto:snrane@niapune.org.in)  
Website: [www.niapune.org.in](http://www.niapune.org.in)

---

**Subject: Changing of Floor and Wall Tiles of PGDM Kitchen, NIA, Pune**

Dear Sir,

NIA invites you to submit your offer as per attached format for the work stated in subject enquiry documents/ Enclosure.

Due Date & Time : 10.06.2022 at 03:00 pm  
Terms & conditions : As per attached Enclosure  
Schedule of Quantities & format for quotation : As per attached Enclosure

**Quotation Evaluation Criterion :**

Quotation complete in all respects should reach at NIA at the above address on or before 03.00 pm of the scheduled date. Quotation received after the due date and time is liable to be rejected. NIA reserves the right to accept or reject any or all quotation received at its absolute discretion without assigning any reason whatsoever.

Thanking You,

Yours truly,

**Executive Engineer**  
**Engg. Dept., NIA**

**ENCLOSURE**

Ref. NIA/ENGG/2022-23/01

Date: 01/06/2022

**Format for quotation**

To be filled by agency

<b>Sr. No</b>	<b>Description</b>	<b>Unit</b>	<b>Rate</b>	<b>Quantity</b>	<b>Amount</b>
1	Dismantling tile work in floors, roofs and walls laid in cement mortar including complete disposal out of campus. For thickness of tiles above 25 mm and up to 40 mm.	Sqm	93.4	160	14944
2	Kota stone slab flooring over 20 mm (average) thick base laid over and jointed with grey cement slurry mixed with pigment to match the shade of the slab, including rubbing and polishing complete with base of cement mortar 1 : 4 (1 cement : 4 coarse sand) 25 mm thick	Sqm	1706.6	75	127995
3	Stone work (machine cut edges in Veneer work) for wall lining upto 10 m height, backing filled with a grout of 12 mm thick cement mortar 1:3 (1 Cement : 3 coarse sand) and jointed with Cement mortar 1:2 (1 cement : 2 stone dust), including grinding area hand grinder on joints rubbing and polishing complete. (To be secured to the backing and the sides by means of cramps and pins which shall be paid for separately). Polished Kota stone slabs on exposed face. 25 mm thick	Sqm	2212.95	60	132777
4	Stone tile work for wall lining upto 10 m height with special adhesive over 12 mm thick bed of cement mortar 1:3 (1 cement : 3 coarse sand), including pointing in white cement with an admixture of pigment to match the stone shade. 8mm thick (mirror polished and machine cut edge) Granite stone of any colour and shade as per direction of Engineer-in-Charge.	Sqm	2675.7	20	53514
5	Plaster of thickness 12 mm to 20 mm including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground, all complete as per direction of Engineer-in-Charge.	Sqm	462.3	60	27738
6	Disposal of moorum/building rubbish/ malba/ similar unserviceable, dismantled or waste material by mechanical transport including loading, transporting, unloading to approved municipal dumping ground for lead upto 10 km for all lifts, complete as per directions of Engineer-in-charge.	Cum.	10	411.3	4113
	<b>TOTAL</b>				<b>361081</b>
	Percentage Above or Below (+/-) or At-par				
	Net Total				
	GST @ 18%				
	<b>Grand Total</b>				
<b>Total In Words:</b>					

**TERMS AND CONDITIONS:**

1. Prices- Rates quoted should be firm.
2. The rates should be quoted on the basis on the units specified in words as well as in figures without any cutting, in case of differences of values / rates in figure and words or any confusion it will be constituted to take the rates which are lowest.
3. Payment- Payment shall be made within 10-15 days after successful completion of work.
4. The quotation should be valid for a minimum period of 60 days from the date of enquiry letter date.
5. The acceptance of items used is subject to inspection by the Engg Dept.
6. In case of transportation work, agency/firm/company shall strictly observe the regulations as laid down by Traffic Police / Motor Vehicle act. NIA shall not be responsible / accountable for violation of these rules. Any damage to NIA property / material during the course of transportation shall be recovered from the agency/firm/company bill.
7. Incomplete quotation will be rejected summarily.

**Signature and seal of contracting agency/firm/company**

**Date:**

**Address:**